

Request for Quotations

Helipad Ambulance Unloading Pad and New Walkway

Location of Work: VOQC Helipad

Scope of work: To construct a 9' by 9', 6" thick concrete pad with a 55' (approximate) long, 6' wide, 4" thick concrete sidewalk branching off the pad to the existing helipad. A new chain link fence gate is to be installed. Details are as follows:

- Concrete Pad is to be built to support vehicle traffic. To be built to BC Building Code standards. Pad is to taper into sidewalk
- Concrete sidewalk is to be built to BC Building Code Standards
- All Concrete is to be at 32mpa strength
- Concrete is to have a medium broom finish
- Concrete pad and sidewalk is to be at existing ground level
- New gate is to be 12' wide and 4' high (same as existing fence). New posts will be required for gate and will have to be concreted in. Hard rock is to be expected for excavation.
- Existing chain gate to be replaced with chain-link fencing
- A site visit can be arranged by contacting Ben Greenough at 250-637-1781

The successful bidder will:

- Be registered with Work Safe BC
- Assume all liability associated with the works being performed

Timeline: Quotations are to be received at the Village office or by E-mail to Ben.Greenough@queencharlotte.ca, no later than 4:00pm Friday October 13th 2017. Work is to be completed no later than November 3rd 2017.